
modular step controller

- 1 Status-LED (CPU-module)
- 2 Service interface for configuration (PC)
- 3 Relay modules
- 4 Power-LED (power supply module)



Brief description:

Continuous controllers from the series 9 can be complemented with subsequently arranged switching steps by the modular step controller 991tz86e. Actuation is performed using the continuous control signal. The configuration of all parameters (setpoint distance, hysteresis, switch-on delay etc.) is done in the CPU-module of the modular step controller by the KFM-PC- software PKS. The modular step controller consists of one CPU- and power supply module each as well as one ore more relay modules with 5 relays each, depending on the number of required switching steps. The step controller can be complemented with 4 relay modules to a maximum of 20 relays. All relays are potential free change over contacts.

In the factory setting, depending on the number of relay modules, the switching points of the steps are evenly distributed throughout the entire control range, however they may be changed as desired. An installed switch-on delay prevents simultaneous switch on of all steps and thus load jumps in the supply mains. It is set jointly for all steps.

Relays which are not needed may be switched off by setting the switch point >100%. The first step may be configured as a modulating output if desired. In parallel, depending on the version, there is a cyclic switching output 0/24V and a continuous control output 0(4)...20mA available for driving a semi conductor switch. This causes an adaption of the power jumps between two steps and thus an almost infinitely variable behaviour.

Version for automatic change-over of the steps

Every change in the output steps causes an automatic change-over of the active steps by activating the next higher output step for power increase and deactivating the lowest output step for power decrease. This forces an approximately even use of all steps including the connected load.

Type summary:

991tz86e. CPU- module (with standard signal 0(4)...20mA, 0(2)...10V measuring input)

991tz870 Relay module with 5 relays


991tz850 Power supply module 100-250 VAC 991tz858 Power supply module 24 V AC/ DC

Device versions:

..Ly Switching output 0/24V max. 40 mA and cont. control output 0(4)...20 mA load <= 500Ω

...z Automatic change-over of the steps

Wiring example:



subject to alterations 991tz8-BE1.doc/2310731

modular step controller Installation and connection

Installation: Before installation inspect the controller for any visible signs of damage caused during transport.

Check power supply acc. to name plate.

Devices in a modular concept are delivered fully assembled on a mounting rail. It can be installed in the control cabinet directly. Alternatively, the modules can be locked in place on the designated monting rail, according to the numbered order, after removing the end pieces and shifting the housing of the modules apart. Then the housing of the modules have to be pushed together. The plug connectors connect the individual modules. In conclusion, both end pieces have to be mounted on both sides of the modular housing.

Electrical wiring:

Plug bar; connect up the controller at the rear following the wiring diagram

- wire cross section max. 1,5 mm²
- To avoid cross interference *all low voltage measuring lines and pilot wires* must be encased in a **shielded cable** (the shielding must be earthed one-sided).
- The control leads must be *fused* externally to protect the output relays.
- Phase wire and neutral wire must not be transposed.
- Connect the modular device and the continuous controller using the supplied patch cable.

Putting into operation:

Switch on power supply. Control lamps, if available, will light up according to their function and the status of the in- and outputs. If nothing happens: Switch off power supply, check electrical connections and other adjustments.

Maintenance:

All electronic controllers in the product range of the manufacturer are virtually maintenance-free. Provided that the controller is correctly installed and put into operation and is protected against mechanical damage and inadmissible operating conditions, it should give years of trouble-free service. *In case of faults* repair work by the customer should be restricted to the externally accessible leads and connections and components the customer is expressly permitted to deal with himself (bridge circuits, fuses).

All further work, especially on internal components will terminate warranty, makes subsequent inspection and fault repair more difficult and can cause considerable damage to the circuitry.

For repair remittance remove plug board with connected leads and the end pieces, shift the housing of the modules apart and remove the individual modules.

In case of remittance please give precise details of the fault to reduce time and cost of repair.

data subjects to alteration 991tz8-BE2.doc / 1110303

modular step controller configuration

Configuration:

*ELo/*EHI for voltage / current input: start / end of display range 0 / 100

tE Switch-on delay per step 1...60sec 5sec

PY.. 991t..p only:

percentage of the output power switched by step .. dep. on no. of steps

Preadjusted: Equal power for each step

SP.. Switch-on points for step 1...20, based on output 0...100% see table

(or deactivation with setting 101%)

Sd.. Switching differences % see table

optional:

rel Switching behaviour of first step:

St (normal step) / CY" (modulating)

Cy" Cycle for cycle behaviour (2...120 sec)

Out Continuous control output signal "0...20 / 4...20" (mA)

4...20mA

st 991t..z only:

function of the steps

static ("stat") or automatic change-over of the steps ("auto") auto

st.. 991t..c only

switching step allocations to the hardware outputs
(right character belongs to output1, character left to it to output 2, etc.).

St3=0011
St4=0100

A "1" means that the accordant hardware output is switched on, if the output signal is higher than the respective switching point. St6=0110 St7=0111

Settings SP.., Sd.. in %, based on internal control signal 0...100%, set not required switching steps to 101%

for switching behaviour St= normal

	SP	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	Sd
3	steps	34	66	97																		31
4	steps	27	50	74	97																	24
5	steps	22	41	59	78	97																19
6	steps	19	34	50	66	81	97															16
7	steps	16	30	43	57	70	84	97														13
8	steps	15	27	38	50	62	74	85	97													12
9	steps	13	24	34	45	55	66	76	87	97												10
10	steps	12	22	31	41	50	59	69	78	88	97											9
11	steps	12	20	29	37	46	54	63	71	80	88	97										9
12	steps	11	19	27	34	42	50	58	66	74	81	89	97									8
	steps	10	17	25	32	39	46	54	61	68	75	83	90	97								7
	steps	10	16	23	30	37	43	50	57	63	70	77	84	90	97							7
	steps	9	16	22	28	34	41	47	53	59	66	72	78	84	91	97						6
16	steps	9	15	21	27	32	38	44	50	56	62	68	74	79	85	91	97					6
17		9	14	20	25	31	36	42	47	53	58	64	69	75	80	86	91	97				6
	steps	8	13	19	24	29	34	40	45	50	55	60	66	71	76	81	87	92	97			5
	steps	8	13	18	23	28	33	38	43	48	52	57	62	67	72	77	82	87	92	97		5
20	steps	8	12	17	22	27	31	36	41	45	50	55	59	64	69	74	78	83	88	92	97	5

for switching behaviour CY= step1 modulating: preadjustments according to the upper table, but: The last point ("97") can be omitted, move all switching steps by one position, switching differences Sd.. uniformly to 0,1 example with 5 steps:

	SF	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	Sd
5 step	S		22	41	59	78																0,1

subjects to alterations 991tz8-BE3.doc / 2310727

Error messages: The status LED of the resp. module signalises the operating state:

CPU- module:

green permanent*: Normal operation

green flashing*: Only with configuration 4..20mA/2..10V:

Measurement line error analogue input

red permanent: The detected module is unsuitable

-> Check the type name of the module, (see type summary)

red flashing: Communication error between one or more other modules

-> Check proper position of the connections beetwen the individual modules

Relay module:

green permanent*: Relay actuated, switched on or switched off depending on the configuration

red flashing: Communication error to the CPU

-> Check proper position of the connections beetwen the individual modules


Power supply module:

green permanent*: Supply voltage on, normal operation

red flashing: Communication error to the CPU

-> Check proper position of the connections beetwen the individual modules

Installation dimensions (each module):



H= 124mm, B = 22,5mm, T = 116mm

Technical data:

Power supply: 100..250VAC, about 12VA, alternative 24V DC/ AC, about 12VA Relay output: 230 V / max. 2 A Logic output: 0/24V max. 40 mA


continuous output 0/4...20mA: load <= 500Ω Housing: for fastening to 35mm mounting rail

Installation orientation: optional

Type of protection: IP20 according to EN 60529 Perm. ambient temp.: 0..60°C, nom. temp 20°C Relative humidity <= 75 % yearly average, (KWF to EN 60529) no condensation

EMC: referring to EN 61326

Connection diagram: (Example, valid for each delivered controller is the wiring diagram on its casing only)



Subject to alterations 991tz8-BE4.doc / 2310727

^{*} alternative yellow, depending on version